



S1	1UD
FAST	2

HW-D-0518 PERPENDICULAR TO FLUTED DECK.
 HEAD OF WALL SYSTEM 1, FAS TRACK PERPENDICULAR UNDER
 FLUTED DECK. 1 AND 2 HOUR FIRE RESISTANT ASSEMBLY
 (SEE UL LISTING FOR WALL FIRE RATING). UL-2079 TEST STD.
 AVAILABLE IN 1 HOUR-SINGLE LAYER OF GYPSUM WALLBOARD