



HW-D-0556 PARALLEL TO BEAM ASSEMBLY.
 HEAD OF WALL SYSTEM 1, PARALLEL TO BEAM ASSEMBLY,
 UNDER FLUTED DECK. 1 AND 2 HOUR FIRE RESISTANT ASSEMBLY.
 (SEE UL LISTING FOR WALL FIRE RATING). UL-2079 TEST STD.
 AVAILABLE IN 1 HOUR - SINGLE LAYER OF GYPSUM WALLBOARD

