



S1	1FD
FASW	2

HW-D-0525 SHAFT WALL AT FLUTED DECK.  
 HEAD OF WALL SYSTEM 1, PERPENDICULAR TO SHAFT WALL  
 UNDER FLUTED DECK. 1 AND 2 HOUR FIRE RESISTANT ASSEMBLY.  
 (SEE UL LISTING FOR WALL FIRE RATING), UL-2079 TEST STD.  
 AVAILABLE IN 1 HOUR - SINGLE LAYER OF GYPSUM WALLBOARD